

PRODUCT MANUAL

Installation & Operation Manual - ACT-SSD-2875 Sliding Sleeve

Document MAN-SSD-2875 | Revision B | 2025-02-17

Product Family	ACT-SSD-2875
Prepared By	A. Gutierrez
Approved By	J. Martinez, P.E.
Document Control	L. Hargrove
Distribution	Field operations, service centers, licensed distributors

Table of Contents

1. GENERAL
2. INSTALLATION
3. SHIFTING OPERATION
4. MAINTENANCE

Product Revision History (from engineering records)

Rev	Date	Description of Change	By
A	2023-04-03	Initial release	A. Gutierrez
B	2025-01-29	Detent ring material to Be-Cu Alloy 25; port count 8 to 12	R. Callahan

1. GENERAL

The ACT-SSD-2875 sliding sleeve provides tubing-to-annulus communication in 2-7/8 in. completions. Working pressure 10,000 psi, temperature 325 degF, NACE MR0175 compliant. The sleeve ships in the CLOSED position with a shipping clip that must be removed at installation.

2. INSTALLATION

- Install flow couplings (ACT-FC-2875) immediately above and below the sleeve in wells with expected rates above 8 MMscf/d or 3,000 bpd.
- Torque EUE connections per TS-200 (1,650 - 2,050 ft-lb for 2-7/8 EUE).
- Record sleeve depth to the nearest 0.5 ft in the completion schematic; the X-profile is at the sleeve TOP.
- Remove the red shipping clip before running.

3. SHIFTING OPERATION

Shift with the ACT-SFT-20 (B-type) shifting tool on slickline. Downward jar action opens the sleeve; upward jar action closes it. The collet detent releases at approximately 350 lbf and resets with an audible/tactile snap at full travel. Full stroke is 2.75 in.

Operation	Tool Position	Jar Direction	Confirmation
OPEN	Engage profile from above	Down	Detent snap; tubing/annulus communication
CLOSE	Engage from below	Up	Detent snap; pressure test tubing
Equalize before opening	N/A	-	Max 500 psi differential before shifting

WARNING: Do not shift with more than 500 psi tubing-to-annulus differential; seal damage will result.

4. MAINTENANCE

The sleeve is redressed at an ACT service center with kit ACT-SSD-2875-RK (two chevron stacks, four o-rings). Recommended redress after 25 shift cycles or per workover. Production hydrotest of each new unit is documented in an HTR report (see HTR-2025-0512).

Document Approval

Role	Name	Signature	Date
Prepared	A. Gutierrez	/signed electronically/	2025-02-17
Quality Review	S. Nguyen	/signed electronically/	2025-02-17
Approved	J. Martinez, P.E.	/signed electronically/	2025-02-17